



Kentrox Modules

Version 2.4.2

Release Notes

May 2015



RELEASE NOTES

Copyright © 2015 by Westell Inc. All Rights Reserved. Westell, Kentrox® and Optima Management System® are registered trademarks of Westell. All other names are trademarks of their respective owners.

Information is correct at time of publication and is subject to change without notice. Contact Westell in Aurora, Illinois to verify current product information. Westell, Inc. is an Equal Opportunity/Affirmative Action employer.

Westell, Inc.
750 North Commons Drive
Aurora, IL 60504 USA
Toll Free: (800) 377-8766
International: +1 (630) 375-4950
Fax: +1 (630) 375-4931

TABLE OF CONTENTS

Table 1 Affected Types	Page 2
Major Features	Page 3
75229 -- Monitor Wireless Modem Signal Strength	Page 3
75210 -- Vanguard TowerLight IR alarm control and alarming	Page 4
75193 -- Support MobileAccess 7.0 active alarm table	Page 5
75145 - Show tower type as status point (A0, E2, etc)	Page 5
74930 -- APC Galaxy 5000 UPS Support	Page 6
75192 - Sensor Offset adjustment for fuel monitoring (pressure sensors)	Page 9
73154 - Support propane tanks for fuel monitoring	Page 10
74343 - Name battery string cell NEs so they maintain cell order	Page 11
75436 - Flash Eagle stops communicating, cannot reconnect	Page 12
Issue List	Pages 13 & 14

Kentrox Modules Release Notes

Version 2.4.2
May 2015

Table 1 Affected Types

Vendor	Models	Configured Types	Issues
APC	Galaxy 5000 *new*	APCGalaxyUPS	74930
Dialight	Medium Intensity, High Intensity, Red Only	DialightMediumIntensityTowerLight , DialightMediumIntensityDiscreteTowerLight , DialightHighIntensityTowerLight , DialightHighIntensityDiscreteTowerLight , DialightRedOnlyTowerLight , DialightRedOnlySmallTowerLight , DialightRedOnlyDiscreteTowerLight , DialightRedOnlySmallDiscreteTowerLight ,	75145
Flash	Eagle, LED	FlashEagle11TowerLight , FlashEagle11DiscreteTowerLight , FlashEagle11EthernetTowerLight , FlashEagle11EthernetDiscreteTowerLight , FlashLEDTowerLight , FlashLEDDiscreteTowerLight	75145
	Vanguard	FlashVanguardSerialTowerLight , FlashVanguardSerialDiscreteTowerLight , FlashVanguardEthernetTowerLight , FlashVanguardEthernetDiscreteTowerLight ,	75145
Mobile Access	SC450	MobileAccessSC450DAS , MobileAccessSC450DiscreteDAS	75193, 75145
BatteryDAQ	M6 *new*	BatteryDAQBatteryMonitor	73154
Westell	Propane Hall Effect *new*	FuelGaugeHallEffectSensor	75145
Westell	Pressure based fuel monitoring	RectangularFuelTankPressureSensor , HorizontalCylinderFuelTankPressureSensor , VerticalCylinderFuelTankPressureSensor	75192

Report Changes

Rectifier reports have been renamed to **Power Supply** so that they would encapsulate for **UPS** and **Rectifier** information.

Major Features

75229 -- Monitor Wireless Modem Signal Strength

If a **Remote** has a wireless modem and the **moduleMonitor** has been configured, the signal strength will be monitored and provided to Optima. The application will create the following information:

Table 2 **Wireless Modem Signal Strength**

Type	Name	Values	Description
measurement	SignalStrength	0.0 - 5.5	Signal strength of the wireless interface
status-point	SignalQuality	VeryPoor, Poor, Fair, Good, VeryGood	Signal quality of the wireless interface

Optima NE Tree

In Optima, if the modem exists and the **moduleMonitor** is configured, a component called **modemMonitor** also will be created. See Figure 1:




Figure 1-1 A **modemMonitor** child network element displays in the NE Tree beneath Site 1234 Monitor

Optima Live View

-- Wireless Signal			
Quality:	Very Good	Strength:	4.1

75210 -- Vanguard TowerLight IR alarm control and alarming enhancement (v3.1 support)

Table 3 Issue 75210 Parameters

Name	Type	Default Value	Options	Description
irAlarmIsNightAlarm	enumeration	enable	disable, enable	Whether IR alarms are bound to night mode
irEnabled	enumeration	enable	disable, enable	Whether or not to enable IR output of capable beacons

New Behavior

```

if irEnabled == "disable":
    ignore IR alarms

ignore IR alarms if irEnabled == "enable" and irAlarmIsNightAlarm ==
"enable":
    TowerCritical (IR ALARM, IR N/A)

if irEnabled == "enable" and irAlarmIsNightAlarm == "disable":
    TowerWarning (IR ALARM, IR N/A)
    
```

Configuration

```

config site network-element towerLight
...
param irAlarmIsNightAlarm [ enable | disable ]
param irEnabled [ enable | disable ]
...
    
```

75193 -- Support MobileAccess 7.0 active alarm table

MobileAccess firmware version 7.0 provided a new pollable SNMP table, the active alarm table. This table provides a similar mechanism to other DAS devices that allows accurate sync of all active alarms on the system. Instead of attempting to walk the

events table (that could contain thousands of entries and still not provide the correct data), the application will use this table.

As with other DAS types, the `MobileAccess` will now fully sync (inventory and active alarms) at startup, periodically (as configured), and on demand (via control).

The application support will only function on a device with a firmware version of 7.0 or greater. We no longer support anything earlier than 7.0. Having an incompatible version will trigger the `IncompatibleVersion` alarm.

No configuration changes are necessary to enable this functionality.

New Alarm

Alarm	Severity	Description
<code>IncompatibleVersion</code>	Critical	Device was polled and an incompatible version was found. Intelligent monitoring is disabled.

75145 - Show tower type as status point (A0, E2, etc)

The FAA identifies different tower types (height, beacon count, etc) with specific style names. The application will "calculate" this style based on its configuration and present the style as a status point. See [Table 4](#) below.

Table 4 Tower Types

Tower Type	AOL?	Beacons	FAA Style	
White	No	6	B2	
		9	B3	
		12	B4	
		15	B5	
		18	B6	
		1	D1	
		2	D1 + 1	
		3	D2	
		4	D2 + 1	
	Yes	6	C2	
		9	C3	
		12	C4	
		15	C5	
		18	C6	
	Red	No	0	A0
			1	A1
			2	A1 + 1
			3	A2
4			A2 + 1	
5			A3	
6			A3 + 1	
7			A4	
8			A4 + 1	
9			A5	
10			A5 + 1	
11			A6	
12			A6 + 1	

Table 4 Tower Types

Tower Type	AOL?	Beacons	FAA Style
Dual	No	1	E1
		2	E1 + 1
		3	E2
		4	E2 + 1
	Yes	6	F2
		9	F3
		12	F4
		15	F5
		18	F6

74930 -- APC Galaxy 5000 UPS Support

Elements

Element	Type	Description
ups	APCGalaxyUPS	Main UPS Controller. Monitors overall UPS information.
upsBattery	APCBatteryString	Monitors battery string information from UPS
upsInputPower	APCPowerMeter	Monitors input power (utility power).
upsOutputPower	APCPowerMeter	Monitors output power (load side)

New Behavior

Added **sync** control action for UPS. UPS syncs automatically on startup. Manual sync will clear additional alarms that cannot be synchronized.

Parameters

Name	Type	Default Value	Options	Description
autoSyncDelay	integer	1440	0 to 1440	Delay between auto sync (in minutes)
cutThroughhhp	string	0.0.0.0		The IP address on which to allow cut-through connections
cutThroughPort	integer	10200	1025 to 65536	The port on which to allow cut-through connections
description	string	<i>empty string</i>		Extra description about this NE
deviceHttpPort	integer	80	1 to 65535	The http port of the device
deviceIp	string			The IP address of the device
deviceSnmpAutoTimeout	enumeration	enable	disable, enable	Whether to automatically adjust the SNMP timeout
deviceSnmpCommunity	string	public		SNMP community string used to poll the device
deviceSnmpGetBulk	enumeration	enable	disable, enable	Whether to use SNMP Get Bulk requests in device walks
deviceSnmpPort	integer	161		SNMP Port of the device
deviceSnmpRetries	integer	2		Number of times to retry SNMP requests
deviceSnmpTimeout	integer	2		Number of seconds to wait for SNMP responses
deviceSnmpTrapCommunity	string	public		SNMP community string in traps received from the device
deviceSnmpVersion	enumeration	V2C	V1, V2C, V3	SNMP Version of the device
model	string	<i>empty string</i>		Extra model information about this NE
snmpManagerIp	string	0.0.0.0		SNMP manager interface IP
snmpManagerPort	integer	1162	1024 to 65535	Unique port for receiving SNMP traps (e.g. 1162)

Example Configuration

Below is an example of simple configuration for the **APC** UPS.

```
config site network-element ups
    type APCGalaxyUPS
    param deviceIp <ipaddress>
```

Supported Reports

AC Line Current

AC Phase Voltage

Battery Charge Level

Battery Current

Battery Temperature

Battery Time Remaining

Battery Voltage

Power Supply Efficiency

Power Supply Output Power

Power Supply Utilization

Ranking: Battery Charge Level

Ranking: UPS Power Failures

Note: Rectifier reports renamed to Power Supply so that they would encapsulate both UPS and Rectifier

75192 - Sensor Offset adjustment for fuel monitoring (pressure sensors)

When monitoring fuel tanks with a pressure sensor, there are varying reasons the sensor may not be able to be installed on the bottom of the tank. This could be to avoid sludge, the way the mounting works, etc. Also, the sensor itself may not be calibrated perfectly to the location of the tank (due to altitude and differences in atmospheric pressure, for example). Therefore, there are new calibration parameters added to compensate for the sensor readings and installation location.

Configuration

Parameter	Options	Default Value	Description
<code>sensorInstallHeight</code>	n/a	0.013	The height of the sensor in the tank (in units as defined by <code>distanceUnits</code> param)
<code>calibrationUnits</code>	PSI, volume	volume	Calibration in PSI or volume (in units as defined by <code>volumeUnits</code> param)
<code>sensorCalibration</code>	n/a	0	The value the sensor reads when the tank is empty (in <code>psi</code> or <code>volumeUnits</code>)

Example Configuration

For example, to configure a sensor in a rectangular fuel tank, but is installed 3 inches from the bottom and is reading 10 gallons when empty, use the following:

```
# in case volume units are not set already
config site param volumeUnits gal
# in case distance units are not set already
config site param distanceUnits in

config site network-element fuelTank
    type RectangularFuelTankPressureSensor
    param capacity 200
    param width 200
    param length 100
    param sensorInstallHeight 3
    param calibrationUnits volume
    param sensorCalibration -10
```

73154 - Support propane tanks for fuel monitoring

To monitor propane fuel tanks, Westell has integrated a Hall effect propane gauge sensor. This sensor provides a 0-100% reading from the actual gauge and then, given a configured tank capacity, calculates current fuel level. From there, fuel monitoring is handled exactly as the pressure based fuel monitoring application.

Configuration

An example configuration for a 500 gallon propane tank using a hall effect sensor:

```
config site network-element fuelTank
    type FuelGaugeHallEffectSensor
    param capacity 500
    param discrete 'analog 1/1'
```

74343 - Name battery string cell NEs so they maintain cell order

When battery cells were added to the dynamicCLI file, they were named Cell1, Cell2, ... Cell10. In Optima, standard alphanumeric ordering would create the list as follows:

```
Cell1
Cell110
Cell111
...
Cell12
Cell13
...
```

Now that battery cells are components and auto created, they are named (and ordered) appropriately as

```
batteryString_Cell_01
batteryString_Cell_02
batteryString_Cell_03
batteryString_Cell_04
....
batteryString_Cell_09
batteryString_Cell_10
batteryString_Cell_11
batteryString_Cell_12
...
```

Fixes

75436 - Flash Eagle stops communicating, cannot reconnect

Flash Eagle can lose communication and not be able to reconnect. **Resolved**

Remove Types

There used to be a need for certain generic NE types. These types, for example **GeneratorControllerPowerMeter**, would work with several different generator types. However, these have been deprecated and now removed in favor of specific NE types, for example **GeneracHTSPowerMeter**. The following types were removed for this reason.

Deprecated Generic Types
GeneratorControllerSplitPhasePowerMeter <i>*removed*</i>
GeneratorControllerThreePhasePowerMeter <i>*removed*</i>
RectifierSplitPhasePowerMeter <i>*removed*</i>
RectifierThreePhasePowerMeter <i>*removed*</i>
RectifierDCPowerMeter <i>*removed*</i>

In addition, there were some "aggregate" types that were never customer implemented. The following types have been removed to remove confusion.

Deprecated Unused Types
AggregateDoor <i>*removed*</i>
AggregateTemperature <i>*removed*</i>
AggregateUPS <i>*removed*</i>

Issue List

<u>Issue ID</u>	<u>Version</u>	<u>Description</u>
75312	2.4.0	SupportBatteryDAQ M6
75229	2.4.0	75229 -- Monitor Wireless Modem Signal Strength
75210	2.4.0	75210 -- Vanguard TowerLight IR alarm control and alarming enhancement (v3.1 support)
75193	2.4.0	75193 -- Support MobileAccess 7.0 active alarm table
75192	2.4.0	75192 - Sensor Offset adjustment for fuel monitoring (pressure sensors)
75145	2.4.0	75145 - Show tower type as status point (A0, E2, etc)
74944	2.4.0	Migrate BatteryDAQ to use component NEs
74930	2.4.0	74930 -- APC Galaxy 5000 UPS Support
74343	2.4.0	74343 - Name battery string cell NEs so they maintain cell order
73154	2.4.0	73154 - Support propane tanks for fuel monitoring
75357	2.4.0	Module Monitor induces Interrupted System Call in FlashEagle11
75259	2.4.0	Andrew ION-M traps are not creating alarms in Optima
75199	2.4.0	Flash Vanguard not Alarming on ALI/QLI Failure
75144	2.4.0	ZTE Rectifier Alarm OIDs not translating in Event View
75079	2.4.0	WorkerSwampedException on FlashVanguardEthernetDiscreteTowerLight
75414	2.4.0	Dialight Small Red controllers do not tell us how many beacons are present
75412	2.4.0	XMLFileCollection alarm needs to clear if an SNMP inventory poll is successful
75326	2.4.0	BatteryDAQ different scale for internal resistance of 12V cells
75290	2.4.0	WorkerQueue alarm never happens
75225	2.4.0	Flash Vanguard not updating mode status point

<u>Issue ID</u>	<u>Version</u>	<u>Description</u>
75188	2.4.0	Debounce writeRegister the same as readRegister for Generac H-Panel Communications Errors
75432	2.4.1	More interrupted system call errors at ATC
75416	2.4.1	Flash Vanguard does not reference device for AOL status
75436	2.4.2	<u>75436 - Flash Eagle stops communicating, cannot reconnect</u>